

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-175-20, 605-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Anadarko Production Co.

Complete Address Box 351, Liberal Kansas 67901

Lease Name Condit Well No. _____

Location C-5W-5E Sec. 17 Twp. 34 Rge. 32 (East)(West)

County Seward Total Depth _____

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargant Casing Pulling

Address _____ License No. 511

Operation Completed: Hour: 11:45AM Day: 26 Month: 8 Year: 19 82

Plugging Operations attended by Agent?: All _____ Part _____ None

The above well was plugged as follows:

They ran 6232' of 4 1/2" production pipe & plugged it back to 5920'. They perforated from 5827' to 33'. 1st plug pumped to bottom, 1 sbx bull & 25 sbx of cement bringing top of cement to 5700'. 2nd plug at 2600' with 25 sbx of cement. 3rd plug at 1625' with 35 sbx of cement. 4th plug on solid bridge at 40' to 0' with 10 sbx of cement. They recovered 3400' of 4 1/2" pipe. The plugging was accomplished by Sargant Casing Pulling.
Amount of Surface Casing: 8 3/8" at 1605'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthie
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I was on another job at this time.

Signed: Paul A. Luthie
Conservation Division Agent

INVOICED
DATE 9-9-82
AMT NO 1062-W

Rec. 9-2-82