

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Diel

WELL NUMBER #1

_____ Ft. from S Section Line

_____ Ft. from E Section Line
C SE/4

SEC. 21 TWP. 34S RGE. 11W (E) or (W)

COUNTY Barber

Date Well Completed _____

Plugging Commenced 3-9-87

Plugging Completed 3-12-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Patton Oil Company

672 W. 4th

ADDRESS Hoisington, Kansas 67544

PHONE#(316) 653-2277 OPERATORS LICENSE NO. 5992

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				13-3/8"	215'	none
				4-1/2"	4620'	3623'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Pumped bottom with 20 sacks ceomon cement mixed with 2 sacks hulls to 4293'. Shot pipe @4000', 3800', 3623', pulled a total of 91 joints of 4-1/2" casing. Plugged surface with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull & 175 cement, 60/40 pos, 6%gel.

(If additional description is necessary, use BACK of this form.) Plugging Complete.

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 19th day of March, 19 87

Irene Hoover
Notary Public

My Commission Expires:



STATE CORPORATION COMMISSION
3-20-87

MAR 20 1987 Form CP-4
CONSERVATION DIVISION
Wichita, Kansas
Revised 07-86

BIG SPRINGS DRILLING, INC.

P.O. BOX 8287
MUNGER STATION
WICHITA, KANSAS 67208

SUITE 29 • 400 NORTH WOODLAWN • (316) 681-1732

January 7, 1980

DRILLERS LOG

Re: Diel # 1
C SE/4
Sec. 21- Twp 34s- Rq 11W
Barber County, Kansas

OPERATOR: Patton Oil Company
CONTRACTOR: Big Springs Drilling, Inc.
COMMENCED: 12-17-79
COMPLETED: 12-31-79

Surface Pipe: 215' of 13 3/4" w/200 sx Common 2% gel 3% ccl


0	215'	Shale, Clay, and Sand
215'	1325'	Shale
1325'	1805'	Shale & Lime
1805'	4615'	Lime
4615'	4630'	Mississippi
4630'		RTD


We certify that the above and foregoing is a true and correct copy of the log on the # 1 Diel located in Barber County, Kansas.

BIG SPRINGS DRILLING, INC.


Paul A. Seymour, Jr.

Subscribed and sworn to before me this 7th day of January, 1980.


Ruth M. Bassett Notary Public

My Commission Expires  My Appt. Exp. _____
May 30, 1983

STATE CORPORATION COMMISSION

JAN 5 1987

CONSERVATION DIVISION
Wichita, Kansas