

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
Form CP-4  
REV. 12-15-80

SEP 20 1982

CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Barber SEC. 20 TWP. 34 RGE. 11W E/W  
Location as in quarters or footage from lines:  
SW NE NW


Lease Owner Mega Petroleum Corporation  
Lease Name Short #1 Well No. \_\_\_\_\_  
Office Address 4849 Greenville Suite 1180 Dallas, Tx. 75206  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 8-27-82  
Plugging completed 9-15-82  
Reason for abandonment of well or producing formation Depleted

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4660'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	330'	none
				4-1/2"	4659'	3495'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped bottom with 35 sacks cement to 3970', shot casing @3908', 3800', 3710', 3608', 3504' and pulled a total of 87 joints of 4-1/2" casing. Plugged well with 3 sacks hulls, 10 sacks gel, 50 sacks cement, 1 sack hulls, 10 sacks gel, released plug and displaced with 100 sacks 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347 Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of September, 1982



My Commission expires:

Irene Hoover  
Notary Public.

DRILLERS LOG

OPERATOR: ~~Edwards Energy Corporation~~ <sup>Now</sup> *MEGA PET. CORP.*  
 4849 ~~4925~~ Greenville, Suite ~~650~~ <sup>1180</sup>  
 Dallas, Texas 75206

LEASE: Short #1  
 SW NE NW Sec. 20-34S-11W  
 Barber County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
 200 Douglas Building  
 Wichita, Kansas 67202

COMMENCED: 6/8/79

COMPLETED: 6/16/79

RTD: 4660

SURF.CSG: 8-5/8" set at 330' with 250 sx cement

PROD.CSG: 4-1/2" set at 4659' with 100 sacks cement

0' to 130' Surface Hole  
 130' to 335' Shale (335' 12 1/4" Surface Hole)  
 335' to 2100' Shale  
 2100' to 4010' Shale & Lime  
 4010' to 4525' Lime & Shale  
 4525' to 4620' Shale & Lime  
 4620' to 4640' Lime & Shale  
 4640' to 4660' Mississippian  
 4660' RTD

ST. D.

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state the above is an accurate copy of the Short #1 log for Edwards Energy Corporation.

*James C. Remsberg*  
 James C. Remsberg

Subscribed and sworn to me this 3rd day of  
 July, 1979

*Mary Lou Taylor*  
 Mary Lou Taylor, Notary

My commission expires January 17, 1981

