

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Barber County. Sec 22 Twp. 34 Rge. 11 (E) (W)

Location as "NE/CNWxSWx" or footage from lines NE NE NE

Lease Owner Purcell & Muller Oil Co. Inc.

Lease Name Schepfacher Well No. 1

Office Address 201 West 27 E Kellogg, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-22 1955

Application for plugging filed 5-22 1955

Application for plugging approved 5-22 1955


Plugging commenced 1:00 P.M. 5-22 1955

Plugging completed 3:00 P.M. 5-22 1955

Reason for abandonment of well or producing formation Dry in (MISS.)

If a producing well is abandoned, date of last production          19        

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Mrs. Riven Prater, Hanson

Producing formation No Ne Depth to top - Bottom 4717 Total Depth of Well 4717 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Red Bud.</u>		<u>0</u>	<u>337</u>	<u>8 5/8</u>	<u>5-8-55</u>	<u>        </u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet for each plug set.

The hole was filled with drlg. mud to within 300' of top of surface casing. 4 set balls were put ahead of first plug. 30 sac cement was then put in through drill pipe, after which hole was filled to within 35 feet of top of casing. 4 set balls were put on bottom of second plug & 30 sac cement was then put in filling hole to top of surface pipes. Job was completed @ approx. 3:00 P.M. 5-22-55.

(the top plug was tied.)

Shanter.

Name of Plugging Contractor Shobe Cementing Co. Hicora, Kansas  
Address         

STATE OF Kansas COUNTY OF Harper, ss.  
Joseph A. Butts (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph A. Butts  
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24 day of May, 1955

My commission expires Jan. 22, 1957  
Maureen Shillard Notary Public.

24-7368-5 3-53-20M  
**PLUGGING**  
WELL SEC 22 T 34 R 11 W  
BOOK PAGE 121 LINE 35

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 25 1955  
CONSERVATION DIVISION  
Wichita, Kansas

ROTARY DRILLERS LOG

COMPANY : Purcell-Mull Drilling Company, Inc. ROTARY DRILLING COMMENCED: 5-8-55  
 Wichita, Kansas

CONTRACTOR : Purcell-Mull Drilling Company, Inc. ROTARY DRILLING COMPLETED: 5-22-55  
 Wichita, Kansas

CASING RECORD: Set 337' of 8 5/8" Surf. Csg. cemented with 225 sacks cement LOCATION: Schupbach #1 110  
 NW NE NE of Sec. 22-34S-27E  
 Barber County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

Sand	25	Sand, Shale & Lime	3992
Red Bed	337	Lime & Shale	4148
Red Rock	555	Shale & Lime	4238
Shale & Shells	918	Lime	4272
Shale & Lime Streaks	1488	Lime & Shale	4332
Shale & Lime	1980	Lime	4378
Lime & Shale	2120	Lime & Shale	4467
Shale & Lime	2990	Lime	4522
Lime & Shale	3207	Lime & Shale	4577
Shale & Lime	3440	Lime	4625
Sand & Shale	3534	Lime & Chert	4655
Shale & Lime	3895	Lime	4717 R.E.T.D.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Purcell-Mull Drilling Co., Inc.

*Frank H. Purcell*  
 FRANK H. PURCELL SECRETARY

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Subscribed and sworn to before me this 1st day of June, 1955.

*Ethel Zimmerman*  
 NOTARY PUBLIC

MY COMMISSION EXPIRES: January 28, 1957.

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 2 1955  
 CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING  
 SEC 22, 34 R 11W  
 BOOK PAGE 121 LINE 35