

STATE OF KANSAS
STATE CORPORATION
COMMISSION
130 South Market Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R. 82-3-117

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 60 days.

15-151-19010-00-00
API NUMBER Drilled 4/19/1961

LEASE NAME Verning Est.

WELL NUMBER 1

1650 Ft. from N / Section Line

3630 Ft. from W Section Line

LEASE OPERATOR G.L.E. Corporation

ADDRESS 518 Washington, Pratt, KS 67124

PHONE # 620-672-2269 OPERATOR'S LICENSE NO. 7701

Character of Well good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/20/2002 (date)

by Scott Alberg (KCC District Agent's Name).

is ACO-1 filed? yes If not, is well log attached? no

Producing Formation Cherokee Depth to Top 4454 Bottom 4462 T. D. 4560 PBTD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	295	None
				4 1/2	4603	2200

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Lay down rods and tubing, sand well back to 4380, dump 4 sx portland cement with dump bailer, stretch and cut 4 1/2 at 2200'
Lay down 4 1/2, run 2 3/8 to 960', load hole with jel and spot 50 sx cement, pull 2 3/8 to 320' and spot 50 sx, pull 2 3/8 to 60' and
Circulate to surface - 60/40, 6% jel, lay down 2 3/8

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, 107 W. Fowler, Medicine Lodge, KS 67104


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: G.L.E. Corporation

STATE OF Kansas COUNTY of Barber, ss.

Alan Vratil (Employee of Operator) or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) *Alan Vratil*

(Address) P.O. Box 187, Medicine Lodge, KS 67104



RECEIVED SUBSCRIBED AND SWORN TO before me this 26 day of March, 2002

MAR 29 2002
KCC WICHITA

Glenda Morrison
Notary Public

My Commission Expires: November 30, 2002

OR