

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt County, Sec. 32 Twp. 27 Rge. (E) 15 (W)

Location as "NE/CNW%SW%" or footage from lines SW SW NE
Lease Owner Musgrove Petroleum Corporation
Lease Name BRYANT Well No. 1
Office Address 801 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed May 6, 1957 19
Application for plugging filed verbally - May 5, 1957 19
Application for plugging approved verbally - May 5, 1957 19
Plugging commenced May 6, 1957 19
Plugging completed May 6, 1957 19
Reason for abandonment of well or producing formation Dry hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 4820' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	318'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 300'
Set 1st plug at 300' w/20 sx cement.
Filled hole with heavy mud to 35'
Set 2nd plug at 35' w/10 sx cement & 1/2 sk hulls.

RECEIVED
STATE CORPORATION COMMISSION

MAY 9 - 1957 05-09-57

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet) Wichita, Kansas
Name of Plugging Contractor Musgrove Petroleum Corporation
Address 801 Union Center, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Wichita
I, Emil E. Bowers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of May, 1957

Dean Faye Hefke
Notary Public.

My commission expires June 16, 1959

PLUGGING
FILE SEC 32 T 27 R 15W
BOOK PAGE 11 LINE 42

CONTRACTOR'S WELL LOG

COMPANY:	Musgrove Petroleum Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	BRYANT #1
LOCATION:	SW SW NE, Sec. 32-27-15W Pratt County, Kansas
COMMENCED:	April 12, 1957
COMPLETED:	May 6, 1957

0	316	Sand, red bed & shale
316	1000	Shale & shells
1000	1015	Anhydrite
1015	1905	Shale & lime streaks
1905	2185	Lime
2185	2443	Lime & shale
2443	2545	Lime, sand & shale
2545	2655	Sand & lime
2655	3496	Lime & shale
3496	3855	Lime
3855	4043	Lime & shale
4043	4420	Lime
4420	4548	Lime & shale
4548	4565	Lime & sandy shale
4565	4600	Cherty lime
4600	4665	Sand & lime
4665	4700	Chert & shale
4700	4734	Shale & cherty sand
4734	4763	Chert & shale
4763	4820	Sand & shale
	4820	Rotary Total Depth

Set 8-5/8" surface casing at 318' with 300 sx cement, 2% calcium chloride.
Dry and abandoned.

ELEVATION:	2063' K. B.	Base K.C.	4393'	4394'	(-2331)
TOPS:	Sample Schlumberger	Chero. Sh.	4533'	4535'	(-2472)
Heebner	3891' 3892' (-1829)	Chero. Sd.	4568'	4546'	(-2483)
Dougl Sh.	3931' 3932' (-1869)	Mississippi	4574'	4575'	(-2512)
Er. Ln.	4057' 4057' (-1993)	Kinder. Sh.	4593'	4595'	(-2532)
Lansing	4074' 4078' (-2015)	Kinder. Sd.	4639'	4642'	(-2579)
		Viola	4675'	4674'	(-2611)
		Sim.. Sh.	4763'	4766'	(-2703)
		Simps. Sd.	4769'	4772'	(-2709)

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the BRYANT #1, SW SW NE, Sec. 32-27-15W, Pratt County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY Emil E. Bowers
Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 8th day of May, 1957.

Dean Jaye Hays
Notary Public

My commission expires June 16, 1959.

<p>PLUGGING FILE SEC 32 T 27 R 15W BOOK PAGE 11 LINE 42</p>
--