

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County. Sec. 30 Twp. 27 Rge. 15W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NW NW
Lease Owner Misco Supply Co.
Lease Name Harper Well No. 1
Office Address 200 MISCO Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 12-31-68
Application for plugging filed 4/3 19 69
Application for plugging approved 4/3 19 69
Plugging commenced 4/4 19 69
Plugging completed 4/9 19 69
Reason for abandonment of well or producing formation Dry hole

NORTH

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production --- --- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph J. Warren, Pratt, Kans.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4738 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Push plug to 4300' - Sand to 4275' - dump 5 sax cement
Shoot & Work pipe at 2618-2505-2415 Pull 78 joints 5 1/2" pipe.
Try to bail hole down - could not bail down.
Globe Cementing Co. pumped 3 sax hulls & 10 sax gel & 75 sax cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 25 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Ralph Comstock Pipe Pulling, Inc.
Address 320 N. Park, Stafford, Kansas 67578

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas R. Sproul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas R Sproul
200 MISCO Bldg., Wichita, Kansas 67202
(Address)

Subscribed AND SWORN to before me this 25th day of April, 19 69
Celeste Kinzie Notary Public.



RECEIVED
 STATE CORPORATION COMMISSION
 APR 3 1969
 CONSERVATION DIVISION
 Wichita, Kansas

DRILLERS LOG

HARPER NO. 1

CASING RECORD:	OPERATOR: Armstrong & Jackman	DESCRIPTION:
8-5/8" @ 277' w/225 sax cement	CONTRACTOR: Sage Drilling Co.	NE NW NW Sec. 30-27S-15W Pratt County, Kansas
TOTAL DEPTH: 4738'	COMMENCED: December 15, 1968	ELEVATION: 2090KB
	COMPLETED: December 29, 1968	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	180	
Shale	180	279	
Sand	279	282	
Red Bed	282	1155	
Shale & Shells	1155	1460	
Shale	1460	1855	
Shale & Lime	1855	1995	
Lime & Shale	1995	2460	
Lime	2460	2607	
Lime & Shale	2607	3025	
Shale	3025	3180	
Lime & Shale	3180	4100	
Lime	4100	4179	
Lime & Shale	4179	4342	
Lime	4342	4439	
Lime & Shale	4439	4567	
Lime, Shale & Sand	4567	4586	
Shale, Chert & Lime	4586	4600	
Shale, Lime & Chert	4600	4726	
Viola	4726	4738	5 1/2" @ 4632' w/125 sax

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
 Wayne W. Kahmeyer

Subscribed and sworn to before me this 30th day of December, 1968.



Louise K. Whitted
 Louise K. Whitted, Notary Public

My commission expires:
 November 26, 1970.