


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Pratt County. Sec. 25 Twp. 27S Rge. 15 (E) (W) X  
Location as "NE/CNW/SE" or footage from lines SE NE SW  
Lease Owner Braden - Deem, Inc.  
Lease Name Tolman Well No. 1  
Office Address Suite 520 200 East First Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19\_\_\_\_  
Application for plugging filed 6-30-70 19\_\_\_\_  
Application for plugging approved 7-1-70 19\_\_\_\_  
Plugging commenced 7-9-70 19\_\_\_\_  
Plugging completed 7-14-70 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4570 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	314	None
				4 1/2	4533	2622.95

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 20 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which \_\_\_\_\_ was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved rig to location.  
Put up pole, measured in, and plugged bottom back to 4425' with sand.  
Dug cellar  
Rigged up jacks. Worked pipe 22 inches stretch at 2500 psi. Dumped 3 sacks of cement on bottom with dump bailer.  
Had hole loaded with salt water.  
Worked pipe, shot pipe at 3320'. Worked pipe, no change in stretch. Shot #2 stopped at 2670'. Shot pipe at 2665', worked pipe loose and pulled 40 joints of casing.  
Finished pulling casing. Pulled a total of 83 joints.  
Loaded the trailer. Set plug at 250 feet with a 10 foot rock bridge. Dumped 6 sacks of cement with dump bailer.  
Bailed hole from 40' to 235'. Fluid stayed down. Filled surface pipe from 235 feet to surface with 3 1/2 yards of ready mix concrete.  
Tore down rig and got ready to move.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.  
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
P. O. Box 221 Great Bend, Kansas  
(Address)



Subscribed and sworn to before me this 17 day of July, 19 70

My commission expires March 24, 1973

Clyde Williams  
Notary Public.

DRILLER'S LOG

Braden Drilling, Inc. et al  
TOLMAN #1  
SE 1/4 SW Sec. 25-27S-15W  
Pratt County, Kansas

Commenced: Jan. 30, 1961

Completed: Feb. 13, 1961

Set 3 5/8" at 312' and cemented  
with 300 sacks cement.

Set 5 1/2" at 4533' and cemented  
with 225 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 1 1970  
CONSERVATION DIVISION  
Wichita, Kansas


Sand and redbed	300 ft.
Shale and shells	312
Redbed and shale	910
Anhydrite	945
Shale, redbed	1475
Shale, shells	2010
Shale and lime	2200
Lime	2560
Lime and shale	3365
Lime	3700
Shale and lime	3880
Lime	4435
Lime and sand	4470
Lime	4570 T.D.

I hereby certify that this is a true and correct log of the above  
captioned well, as shown by the daily drilling reports.

  
F. M. Callaway

Subscribed and sworn to before me this 21st day of December, 1961.

My commission expires March 21, 1962

  
Helen Schultz, Notary Public