


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plot

Morton County. Sec. 36 Twp. 34 Rge. 40 (E) (W)
Location as "NE/CNW/SW" or footage from lines C SW
Lease Owner Anadarko Production Company
Lease Name Hayward "A" Well No. 2
Office Address P. O. Box 351, Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 17 19.62
Application for plugging filed November 19 19.62
Application for plugging approved 19
Plugging commenced November 17 19.62
Plugging completed November 17 19.62
Reason for abandonment of well or producing formation Dry
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott
Producing formation Depth to top Bottom Total Depth of Well 6818 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None				8 5/8"	1699'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Spotted 150 sacks cement from 2850' to 2400', spotted 45 sacks cement @ 700', spotted 15 sacks from 50' to 5'.

RECEIVED
STATE CORPORATION COMMISSION

NOV 21 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Moran Brothers, Incorporated
Address 1200 Oil & Gas Building, Wichita Falls, Texas

STATE OF KANSAS COUNTY OF SEWARD, ss.

S. H. Neithercoat (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

S. H. Neithercoat, Superintendent
P. O. Box 351, Liberal, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November, 1962

My commission expires

MY COMMISSION EXPIRES SEPT. 29, 1964

Notary Public.

DRILLER'S LOGWELL NAME Hayward "A"COMPANY OPERATING Anadarko Production Company
ADDRESS of COMPANY Box 351, Liberal, KansasWELL LOCATION C ½ SW ½ ½,1373 ft. North of South line,1272 ft. East of West line; Sec. 36 Twp. 34 Rge. 40, Morton County, KansasDRILLING STARTED October 29, 19 62 DRILLING COMPLETED November 17, 19 62WELL COMPLETED November 17, 19 62 WELL CONNECTED _____, 19 _____ELEVATION 3345.9 ft. Ground Level CHARACTER OF WELL (Oil, Gas, or Dry Hole) Dry Hole

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
None					

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8"	1699'	900	None

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Sand, Red Bed, Gypsum	0	776	Lime & Shale	4224	5364
Sand, Red Bed	776	1219	Cherty Lime	5364	5410
Anhydrite & Sand	1219	1700	Shale & Lime	5410	6018
Sand, Anhydrite & Shale	1700	1859	Shale & Sand	6018	6189
Gypsum & Anhydrite	1859	2279	Lime & Shale	6189	6697
Gypsum, Shale & Anhydrite	2279	2762	Lime	6697	6818
Shale & Lime	2762	3184	Total Depth	6818	
Lime, Sand & Shale	3184	3364			
Lime & Shale	3364	3834			
Lime	3834	3901			
Lime & Shale	3901	3985			
Lime	3985	4224			

RESULTS of INITIAL PRODUCTION TEST: None