

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME MILLEMOR

WELL NUMBER 2-27

1370 Ft. from S Section Line

1170 Ft. from E Section Line

SEC. 27 TWP. 34S RGE. 40 (W)

COUNTY Morton

Date Well Completed 9/4/68

Plugging Commenced 9/22/87

Plugging Completed 9/22/87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR PAN EASTERN EXPLORATION COMPANY

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 5589

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/21/87 (date)

by Glen Barlow (Dodge City) (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Driller's Log Attached

Producing Formation Glorietta Depth to Top 1294 Bottom 1344 T.D. 1390

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Glorietta</u>	<u>Salt water</u>	<u>1268</u>	<u>1390</u>	<u>2-7/8</u>	<u>1380</u>	<u>-0-</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped 1/4 sx hulls followed by 40 sxs common cement from 1380-3'. Cut off and capped well.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547


Address 620 South Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.

M. L. Pease, Division Production Manager (Employee of Operator) or Operator of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.

(Signature) M. L. Pease

(Address) Box 351, Liberal, Kansas 67901



before me this 10th day of December, 19 87
Beverly J. Williams
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1987

DRILLER'S LOG

Panhandle Eastern Pipe Line Co.

WELL NAME: Millemon No. 2-27 ; COMPANY OPERATING: ~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~
 ADDRESS of COMPANY: Box 828 Liberal, Kansas 67901

WELL LOCATION: 1/4 1/4 1/4,
1370 ft. North of South line,
4110 ft. East of West line: Sec. 27, Twp. 34, Rge. 40, Morton County, Kansas

DRILLING STARTED 8-28, 1968; DRILLING COMPLETED 8-29, 1968
 WELL COMPLETED 9-3, 1968; WELL CONNECTED _____, 19____

ELEVATION: 3369 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) SWD

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Glorieta	1324	1344	40	500	15% HCL
	1297	1314			

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
2-7/8	1384	340	none

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Sand Clay & Shale	0	1172			
Gyp & Anhydrite	1172	1220			
Sand	1220	1390			

RESULTS of INITIAL PRODUCTION TEST: Salt water disposal well, gravity - 1.13 bbls per min.

STATE OF KANSAS - DEPARTMENT OF REVENUE

JUL 27 1987

15-129-20027-0000

DRILLER'S LOG

Panhandle Eastern Pipe Line Co.

WELL NAME: Millemon No. 2-27 ; COMPANY OPERATING: ~~XXXXXXXXXXXXXXXXXXXXXXXXXX~~

ADDRESS of COMPANY: Box 828 Liberal, Kansas 67901

WELL LOCATION: 1/4 1/4 1/4,
1370 ft. North of South line,
4110 ft. East of West line: Sec. 27, Twp. 34, Rge. 40, Morton County, Kansas.

DRILLING STARTED 8-28, 1968; DRILLING COMPLETED 8-29, 1968.
WELL COMPLETED 9-3, 1968; WELL CONNECTED _____, 19____

ELEVATION: 3369 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) SWD

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Glorieta	1324	1344	40	500	15% HCL
	1277	1314			

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
2-7/8	1384	340	none

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Sand Clay & Shale	0	1172			
Gyp & Anhydrite	1172	1220			
Sand	1220	1390			

RECEIVED
STATE CORPORATION COMMISSION

DEC 14 1967

CONSERVATION DIVISION
Wichita, Kansas

RESULTS of INITIAL PRODUCTION TEST: Salt water disposal well, gravity - 1.13 bbls per min.