

15-129-00064-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Morton County, Sec. 16 Twp. 34S Rge. 40 (X) (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW

Lease Owner Hamilton Brothers, Inc.

Lease Name Don J. Dallas Well No. 1-16

Office Address P. O. Box 1886, Midland, Texas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-7-59 19

Application for plugging filed 12-7-59 19

Application for plugging approved 12-7-59 19

Plugging commenced 12-8-59 19

Plugging completed 12-8-59 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Broadfoot

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 6320 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	2705	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

No. 1 Plug; spotted cement plug from 6320' to 6212'; 24 sx.

No. 2 Plug; spotted cement plug from 2730 - 2560; 40 sx.

No. 3 Plug; spotted cement plug 30' 50 surface; 8 sx

STATE CORPORATION COMMISSION
DEC 21 1959
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Halliburton (If additional description is necessary, use BACK of this sheet)
Address Hugoton, Kansas

STATE OF Texas COUNTY OF Potter, ss.
W. P. von Osinki (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. P. von Osinki
532 Petroleum Building, Amarillo, Texas (Address)

SUBSCRIBED AND SWORN TO before me this 18 day of December, 1959

My commission expires June 1, 61

DALE PURNOS Notary Public

DALE PURNOS, Notary Public
Potter County, Texas

Lease: Don J. Dallas No. 1-16
 Operator: Hamilton Brothers, Inc.
 Contractor: Carl B. King
 Comm: 11-17-59 Comp: 12-7-59

Location: SE SE NW
 Section 16-34S-40W
 Morton County, Kansas
 Casing: 8 5/8" Set @ 2705

Elevation: 3361 G. L.

Surface Sands & Gravel	0	650
Red Beds	650	1000
Anhydrite	1000	1250
Red shale, Sand, Anhy, Lime	1250	2500
Lime, shale, sands.	2500	2750
Limestone	2750	4000
Lime, Shale, Sands	4000	4250
Lime w/shale stringers	4250	4900
Cherokee Shale	4900	5000
Cherokee Limestone	5000	5150
Shale w/lime stringers	5150	5600
Atoka limestone	5600	5650
Morrow Shale	5650	6120
Lower Morrow Sand	6120	6170
Mississippian Lime - Shale	6170	6320

STATE OF TEXAS)
 COUNTY OF POTTER)

STATE OF KANSAS
 COMMISSIONER OF
 CONSERVATION DIVISION
 Wichita, Kansas
 DEC 21 1959

I hereby certify that the above is a true and correct copy of the log on the Don J. Dallas No. 1-16 well, located SE SE NW Section 16-34S-40W, Morton County, Kansas.

Hamilton Brothers, Inc.

BY: W. P. von Osinski
 W. P. von OSINSKI

Subscribed and sworn before me this 18th day of December 1959.

DALE BURNS

DALE BURNS, Notary Public
 Potter County, Texas

My commission expires June 1, 1961/