

15-191-00612-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

NORTH

Locate well correctly on above
Section Plat

Sumner County. Sec. 26 Twp. 34 Rge. (E) 1 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NE SE

Lease Owner. Herndon Drilling Company

Lease Name Smith Well No. 1

Office Address: Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole)..... **Dry**

Date well completed. 3-18 19 54

Application for plugging filed 3-18 19 54

Application for plugging approved	3.18	19.54
-----------------------------------	------	-------

Plugging commenced.....	3-18	19 54
-------------------------	------	-------

Plugging commenced.....	3-18-54	19 54
Plugging completed.....	3-18-54	19 54

Reason for abandonment of well or producing formation.....Dry

If a producing well is abandoned, date of last production..... 19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well.....W. G. Buffington.....

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 4416 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Hole was filled with rotary mud to 320 feet. Bottom plug was set at 320 feet and 2 sacks of hulls was poured in. Cemented with 125 sacks of cement. Cement was mixed with a cementing truck - Sun Cementing Co. Arkansas City, Kansas.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....Herndon Drilling Company.....

Address.....Drawer 489, Tulsa, Oklahoma.....

STATE OF Oklahoma COUNTY OF Tulsa ss
 Vienna, Kansas

STATE OF _____, COUNTY OF _____, SS:
Tom Elliott (employee of owner) or ~~owner or operator~~ of the above-described well

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Tom Elwood

SUBSCRIBED AND SWORN to before me this 23rd day of March, 1954)

My commission expires, Sept. 19, 1956 *[Signature]* Notary Public.

PLUGGING
FILE SEC 26 T 34 P 1W
BOOK PAGE 21 LINE 8

WELL LOG ON SMITH #1

Spudding date: 2/26/54
 Date casing set: 2/26/54
 Date rotary completed: 3/18/54
 Date cable completed:

Location:
 Sec. 26-34S-1W - Sumner Co., Kansas

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>	<u>REMARKS</u>
0	155	Surface Hole	Ran 10 Jts. 8-5/8" 24# Casing @ 323.66'
155	324	Shale & Shells	Less Threads - Pipe Set @ 323 Ft.
324	2705	Shale & Lime	Cemented w/ 200# CC & 225 Sx.
2705	2900	Shale & Sand	
2900	3140	Shale & Lime	
3140	3362	Shale & Shells	
3362	3600	Shale & Lime	
3600	3765	Lime	
3765	3830	Lime & Shale	
3830	3879	Lime	
3879	3960	Lime & Chert	
3960	4246	Lime	
4246	4278	Sand	
4278	4326	Sand & Shale	
4326	4407	Lime	
4407	4416	Dolomite	
4416		Total Depth	

Plugging Record:

Filled hole to 320' w/ rotary mud
 Set plug & bridged w/ 2 Sx. Bulk
 Filled hole w/ 125 Sx. of Cement

VED
 COMMISSION

APR 23 1954

MINING DIVISION
 Topeka, Kansas

Subscribed and sworn to before me this 24th
 day of March, 19 54

I certify the above and foregoing to be a true and exact
 copy of the original driller's log on the SMITH #1

HERNDON DRILLING COMPANY

Ray M. Measuring
 Notary Public
 My commission expires: 4-22-57

By: *P. J. Moore*
 Title:

Assistant Secretary

