

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

OR

Strike out upper line  
when reporting plug-  
ging of formations.

FORMATION PLUGGING RECORD

Sumner County, Sec. 26 Twp. 34 Rge. 1 ~~W~~ (W)  
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW/4 SW/4 NW/4  
Lease Owner Earl F. Wakefield, et al  
Lease Name Geeslin Well No. 1  
Office Address  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 8 1950  
Application for plugging filed November 8 1950  
Application for plugging approved November 8 1950  
Plugging commenced November 8 1950  
Plugging completed November 8 1950  
Reason for abandonment of well or producing formation

NORTH


Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 4322 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	150'	150'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 150 ft. pushed wood plug to 150 ft., cemented with 15 sacks, filled with heavy mud to 25 ft. bridged with wood plug cemented to bottom of cellar with 10 sacks.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 18 1950  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to Earl F. Wakefield  
Address 307 Union Natl. Bank Bldg.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Earl F. Wakefield*

(Address)

SUBSCRIBED AND SWORN to before me this 13th day of November 1950.

My commission expires 12-23-50 *Jeannie Gaffney* Notary Public.

PLUGGING  
FILE SEC 26-T-34 R 10  
BOOK PAGE 41 LINE 12

Geeslin #1  
Owner: Earl F. Wakefield et al  
Contractor: Earl F. Wakefield  
Comm: 10-20-50 Comp: 11-9-50

SW/4 SW/4 NW/4  
26-34-1W  
Summer County, Kansas  
Casing: 150' of 8 5/8"

Surface	150
Shale, Shells & Red Rock	285
Lime	320
Lime & Shale	510
Shale & Lime Shells	645
Shale Shells	742
Shale	825
Lime & Shale	1850
Shale	1930
Sandy Shale & Lime Streaks	2030
Lime	2165
Shale & Lime	2810
Lime, Sand & Shale	2817
Sand	2840
Lime & Shale	2845
Sand & Shale	2925
Shale & Lime	3209
Sand Hard	3235
Sand	3288
Lime & Shale	3873
Lime	3880
Shale & Lime	3940
Lime	3969
Lime & chert	4048
Lime, chert & shale	4060
Lime & chert	4102
Lime, chert & shale	4125
Lime & Shale	4142
Lime	4230
Lime & Shale	4285
Shale	4297
Sand	4322
T. D.	4322

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 18 1950  
CONSERVATION DIVISION  
WICHITA, KANSAS

I hereby certify that the above is a true and correct copy of the log of the Geeslin #1 well located SW/4SW/4 NW/4, 26-34-1W, Summer County, Kansas.

Earl F. Wakefield

Subscribed and sworn to before me this 8th day of November, 1950.

P. James Payne

By Commission Expires: 12-25-50

PLUGGING  
WELL NO. 26-34-1W  
DATE NOV 18 1950