
15-191-00461-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Sumner County. Sec. 34 Twp. 34 S Rge. (E) 1 (W)
Location as "NE/CNW¼SW¼" or footage from lines SE SE SE
Lease Owner Herndon Drilling Company
Lease Name McProud Well No. 1
Office Address 423 Mayo Building, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 3-5-53 19
Application for plugging filed 3-5-53 19
Application for plugging approved 3-5-53 19
Plugging commenced 3-5-53 19
Plugging completed 3-5-53 19
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Buffington
Producing formation Depth to top 40' Bottom 300' Total Depth of Well 4279 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 40 feet to 300 feet for each plug set.

Hole was filled with heavy rotary drilling mud to 300 ft. and bottom plug was spotted with 15 sacks cement. Hole was filled to 40 ft. from Rotary Table bushings. Top plug was spotted and 10 sacks of cement on top

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1953
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Herndon Drilling Company
Address Tulsa, Oklahoma

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

Jack Herndon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [signature]

Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of March, 19 53

[signature]
Notary Public.

My commission expires Sept. 19, 1956

23-8390-s 6-51—20M

PLUGGING
FILE SEC 34 T 34 R 1E
BOOK PAGE 82 LINE 41

15-191-00461-0000

WELL LOG ON McPROUD #1

Spudding date: 2-17-53
Date casing set: 2-18-53
Date rotary completed:
Date cable completed:

Location: Sec. 34-34S-1W - Sumner Co., Kansas

FROM	TO	FORMATION	REMARKS
0	302	Shale & Sand	Ran 10 Jts. 8-5/8" 24# J-55 Casing
302	810	Shale & Shells	Set @ 302'
810	2632	Lime & Shale	Cemented w/ 225 sxs. Cement.
2632	3406	Sand & Shale	
3406	3450	Shale & Lime	
3450	3710	Lime	
3710	3830	Lime & Shale	
3830	3970	Lime	
3970	4035	Lime & Chert	
4035	4240	Lime	
4240	4279	Shale	

Plugging Record:

Bottom Plug @ 300'
15 Sxs. Cement

Top Plug @ 40'
10 Sxs. Cement

Subscribed and sworn to before me this 12th day of March, 1953

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1953
CONSERVATION DIVISION
Wichita, Kansas

Notary Public
My commission expires: 8-28-55

I certify the above and foregoing to be a true and exact copy of the original driller's log on the McProud #1

HERNDON DRILLING COMPANY

By: C. J. Moore
Title: Assistant Secretary

PLUGGING
FILE SEC 34 T 34 R 1W
BOOK PAGE 82 LINE 41

HD-38