

15-191-00036-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4



Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

### WELL PLUGGING RECORD

Sumner County. Sec. 35 Twp. 34S Rge. (EX) 1 (W)

Location as "NE/CNW%SW%" or footage from lines. SE NW NE

Lease Owner Jones-Gebert Oil Co.

Lease Name Bacon Well No. 1

Office Address 1007 Central Bldg. - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 15 1962

Application for plugging filed June 15 1962

Application for plugging approved June 15 1962


Plugging commenced June 15 1962

Plugging completed June 15 1962

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well H. E. Hess

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4231 Feet

Show depth and thickness of all water, oil and gas formations.

#### OIL, GAS OR WATER RECORDS

#### CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	225'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set 235' of 1/2 sx. hulls, 18 sx. cement. Mudded up to 37', 1/2 sx. hulls, set plug, 10 sx. cement, 2 sx. cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
6-22-62  
JUN 22 1962

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jones-Gebert Oil, Inc.

Address 1007 Central Bldg. - Wichita, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.

George R. Jones (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George R. Jones

1007 Central Bldg. - Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of June, 1962



Barbara J. Layton  
Notary Public.

My commission expires February 1, 1964



DRILLERS' LOG

Company: Jones-Gebert Oil, Inc.  
 Contractor: Jones-Gebert Oil, Inc.  
 Farm: Bacon #1  
 Location: SE NW NE, Sec. 35-34S-1W  
 Sumner County, Kansas  
 Commenced: 5-29-62  
 Completed: 6-15-62  
 Casing: 8-5/8" @225' w/175 sx.

0	-	170	Surface clay
170	-	224	Cement
224	-	290	Shale and lime streaks
290	-	400	Lime
400	-	693	Shale and lime streaks
693	-	885	Shale and lime
885	-	1040	Shale and lime
1040	-	1420	Shale and lime streaks
1420	-	1620	Shale and lime
1620	-	1830	Shale and lime
1830	-	1938	Lime and shale
1938	-	2055	Lime w/shale steaks
2055	-	2145	Shale and lime streaks
2145	-	2300	Shale w/lime streaks
2300	-	2435	Shale and lime streaks
2435	-	2530	Lime and shale
2530	-	2650	Lime and shale
2650	-	2776	Shale and lime
2776	-	2909	Shale and sand
2909	-	2982	Lime and shale
2982	-	3062	Lime and shale
3062	-	3173	Shale
3173	-	3240	Layton sand
3240	-	3295	Shale and lime
3295	-	3362	Shale and lime
3362	-	3418	K.C.
3418	-	3503	K.C. and shale
3503	-	3560	Lime and shale
3560	-	3615	Lime and shale
3615	-	3683	Lime and shale
3683	-	3750	Lime and shale
3750	-	3790	Shale and lime
3790	-	3852	Lime and shale
3852	-	3875	Lime and shale
3875	-	3905	Miss. lime
3905	-	3912	Miss.
3912	-	3933	Miss.
3933	-	3959	Miss. lime and chert
3959	-	3981	Miss. lime and chert
3981	-	4002	Miss. and shale
4002	-	4024	Miss. lime and chert
4024	-	4046	Miss. lime and chert
4046	-	4055	Miss. chert and lime
4055	-	4071	Miss. lime
4071	-	4093	Miss. lime and shale
4093	-	4115	Miss. lime and shale
4115	-	4151	Miss. lime

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 22 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

4151	-	4187	Kinderhook
4187	-	4208	Kinderhook
4208	-	4220	Kinderhook shale
4220	-	4226	Simpson sand
4226	-	4230	Simpson
		4231	Rotary Total Depth

I, George R. Jones, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Bacon, SE NW NE, Sec. 35-34S-1W, Sumner County, Kansas as reflected by the files of Jones-Gebert Oil, Inc.

*George R. Jones*  
George R. Jones

State of Kansas        )  
                                  ) ss:  
County of Sedgwick    )

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 20th day of June, 1962.



*Barbara J. Layton*  
Barbara J. Layton, Notary Public

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUN 22 1962  
CONSERVATION DIVISION  
Wichita, Kansas