

15-191-00442-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Sumner County. Sec. 14 Twp. 34 Rge. (E) 2 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NE $\frac{1}{4}$ NE $\frac{1}{4}$ SE $\frac{1}{4}$
Lease Owner Fred U. T. Smith, A. F. Carson
Lease Name Boatright Well No. 1
Office Address 801 Union National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed May 12, 1948
Application for plugging filed May 11, 1948
Application for plugging approved May 11, 1948
Plugging commenced May 12, 1948
Plugging completed May 12, 1948
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W. G. Buffington
Producing formation Depth to top Bottom Total Depth of Well 4700 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface casing	207'	8 5/8" casing	cemented with	150	sax cement	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set wood plug at 215 ft. and 15 sax cement placed on top of wood plug;
set wood plug 20 ft. below ground level, filed to top with 10 sax cement.

May 26 1948
5-26-48

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to H & T Drilling Company
Address P. O. Box 36, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
W. L. Copeland (employee or owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. L. Copeland
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 25 day of May 1948
Notary Public.

My commission expires October 15, 1949

PLUGGING
FILE SEC 14 T 34 R 2W
BOOK PAGE 28 LINE 38

Fred U. T. Smith & A. F. Carson
 Boatright Well #1
 Northeast Quarter of the Northeast Quarter of the Southeast Quarter
 (NE $\frac{1}{4}$ NE $\frac{1}{4}$ SE $\frac{1}{4}$) Sec. Fourteen (14), Twp. Thirty-four (34), Range Two West (2W)
 Sumner County, Kansas.

Starting date April 2, 1948
 Plugging date May 12, 1948

Formation	Depth	Formation	Depth
Shale & Sand	0 75	Shale	2895 2960
Shale & Shells	75 247	Shale & Sand	2960 3065
Shale & Lime Shells	247 310	Lime & Shale	3065 3100
Shale & Lime	310 505	Shale	3100 3225
Lime & Shale	505 610	Shale & Shells	3225 3285
Lime	610 660	Lime & Shale	3285 3330
Sand	660 670	Shale & Shells	3330 3365
Sandy Shale	670 705	Shale & Sand	3365 3470
Shale & Sand	705 825	Lime	3470 3665
Lime & Shale	825 920	Shale	3665 3695
Sand, Lime & Shale	920 1045	Shale & Lime	3695 3805
Shale & Shells	1045 1115	Lime	3805 3850
Lime & Shale	1115 1195	Lime & Shale	3850 4060
Shale, Lime & Red Rock	1195 1295	Shale	4060 4090
Shale & Lime	1295 1370	Chert & Shale	4090 4100
Lime & Shale	1370 1505	Chert	4100 4125
Shale	1505 1630	Chert & Lime	4125 4145
Lime & Shale	1630 1850	Lime	4145 4319
Shale	1850 2010	Chert & Lime	4319 4323
Lime & Shale	2010 2130	Lime	4323 4369
Shale & Shells	2130 2180	Lime & Chert	4369 4425
Sandy Lime & Shale	2180 2255	Lime	4425 4454
Lime & Shale	2255 2365	Chert & Lime	4454 4467
Lime	2365 2410	Lime	4467 4477
Lime & Shale	2410 2445	Shale	4477 4505
Lime	2445 2500	Shale & Lime	4505 4550
Lime & Shale	2500 2560	Sand	4550 4570
Shale	2560 2620	Sand & Shale	4570 4659
Lime & Shale	2620 2655	Sand	4659 4679
Shale & Iron	2655 2685	Lime	4679 4700
Sand & Shale	2685 2740	Total Depth	4700
Lime & Shale	2740 2895		

I, W. L. Copeland, drilling superintendent for the H & T Drilling Company, who drilled the above named well certify the log presented above is to the best of my knowledge correct.

W. L. Copeland MAY 26 1948

Great Bend, Kansas

Subscribed and Sworn to before me this 25th day of May, 1948

V. F. ...
 Notary Public

My commission expires Oct. 15, 1949

PLUGGING
 FILE SEC 14 T 34 R 2W
 BOOK PAGE 28 LINE 38