

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION

SEP 19 1966

CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Cities Service Oil CompanyComplete Address: Box 1028, Guymon, OklahomaLease Name Mingenback, "B" Well No. 1Location C SE NW Sec. 18 Twp. 34 Rge. 40 (N) (W)County Morton Total Depth 6510'Abandoned Oil Well X Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: NonePlugging Contractor: Daco Lease & well ServiceAddress: Borger, Texas License No. 138Operation Completed: Hour 5:30PM Day 15 Month 9 Year 1966

The Above well was plugged as follows:

8 5/8" to 1651' Circulated w/ cement. 4 1/2" to 5570' cemented.Top perforations 5491' All Perforations Squeezed off.Top of cement 5420' Mud 5420' to 2440'Spotted 50 sacks cement 2440' to 2285' Mud 2285' to 704'Spotted 35 sacks cement 704' to 604' Mud 604' to 34'Plug, Halls & 10 sacks cement 34' to 0'.Pulled 2440' of 4 1/2" casing. Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/19/66INV. NO. 3949-4Signed: Edgar J. Eves
Well Plugging Supervisor