

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 19 1965

Operator's Full Name Panhandle Eastern Pipe Line Co. Wichita, Kansas CONSERVATION DIVISION

Complete Address: Box 828 Liberal, Kansas

Lease Name Crawford Well No. # 1-32

Location C NE Sec. 32 Twp. 33S Rge. 37 (E) (W)

County Stevens Total Depth 2851'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Sargent Casing Pulling Co.

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 8 PM Day 17 Month 20 Year 65

The Above well was plugged as follows:

12 1/2"-569' Circulated w/cement. 8 5/8"-2575' Cemented. 4 1/2"-1990'

Linner set at bottom 4 1/2" to 2767' Plug back to 2767'

Plug bottom w/125 Sax.cement: 2767' to 2363' Mud 2363' to 650'

Spotted 110 Sax.cement 650' to 485' Mud 485' to 30'

Plug, Hulls, 15 Sax.cement 30' to 0 Weld cap on surface pipe, cut surface
off 5' below ground level. Pulled 1990' 4 1/2" pipe. Pulled 903" 8 5/8" pipe.

Company pump.

I hereby certify that the above well was plugged as herein stated.

DATE 2/19/65
INV. NO. 0704-W

Signed [Signature]
Well Plugging Supervisor