

Plug Back

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. 52-1LOCATION Center of NW/4SEC. 8 TWP. 33 RGE. 37WDry Hole Abandoned Oil Well Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 2 Lease RatcliffOperator Republic Natural Gas Address Hugoton, KansasField Hugoton County StevensTotal Depth 2815 Feet.

(Describe briefly the manner in which the well was plugged)

Clean out to Total Depth. Ran2660 feet of 2" tubing, spotted20 bbls. of heavy mud. Killed wellby pumping water into angular space.Pulled tubing up to 2460 feet andspotted 25 sacks of regular cement.Cement plug from 2460 feet to 2560 feet.R. J. PhillippeDistrict Conservation AgentDate June 8, 1946