

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 12 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Mobil Oil Corp.  
Complete Address Box 400, Hugoton, Kansas  
Lease Name Smith Well No. 1  
Location C SW Sec. 13 Twp. 33 Rge. 37 (E) (W)  
County Stevens Total Depth 2805'  
Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X  
Other well as hereafter indicated None  
Plugging Contractor J.D. Well Service  
Address Liberal, Kansas License No. 622  
Operation Completed: Hour 9:30AM Day 7 Month 7 Year 1971

The above well was plugged as follows:

12 1/2" to 577' circulated w/ cement. 8 5/8" to 2571' circulated w/ cement.  
7" liner 2537' to 2805' Plug bottom w/ 50 sacks cement  
Top of cement. 2138' Mud 2138' to 623'  
Spotted 35 sacks cement 623' to 500' Mud 500' to 60'  
Plug. H 11s & 15 sacks cemen 60' to 0'. Halliburton Pump Truck.  
No pipe pulled.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edward Eves  
Well Plugging Supervisor

DATE 7/14/71  
INV. NO. 3989-W