

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 18 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Jack H. Vaughn Engineering Company

Complete Address 708 1st National Center, Oklahoma City, Oklahoma 73102

Lease Name Hays "A" Well No. 1

Location App C SW Sec. 4 Twp. 34 Rge. 31 (E) (W)

County Seward Total Depth 6000'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargent Casing Pulling

Address Box 506,, Liberal, Kansas License No. 511

Operation Completed: Hour 5:00PM Day 12 Month 4 Year 1974

The above well was plugged as follows:

8 5/8" to 1455' circulated w/ cement. 4 1/2" to 5770' cemented.

Top perforations 5645' Plug bottom w/ 20 sacks cement.

Top of cement 5545' Mud 5545' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls * 15 sacks cement 45' to 0'. Company Pump

Pulled 3030' of 4 1/2" casing.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 4/18/74

INV. NO. 8951-W

Signed: [Signature]
Well Plugging Supervisor