

15-175-10211-0000

Form CP-3
Rev. 6-26-62

J
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 30 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name AJ. Curtiss & Mahoney

Complete Address: Box 1257 Liberal, Kansas

Lease Name Dowdy Well No. # 1-31

Location C NW SE Sec. 31 Twp. 34 Rge. 34 (E)/(W)

County Seward Total Depth 6752'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 1 PM Day 28 Month 3 Year 65

The Above well was plugged as follows:

13 3/8"-735' Circulated w/cement. 9 5/8"-2905' Cemented.

4 1/2"-6750' Cemented. Bridge plug set at 4400'. Perforations 4360' to 4365'

Plug bottom w/20 Sax.cement top cement at 4178'. Mud 4178' to 700'

Spotted 35 Sax.cement 700' to 600' Mud 600' to 45'

Plug, Hulls, 15 sax.cement 45' to 0 Pulled 2946' 4 1/2" pipe.

Company Pump. No 9 5/8" pipe pulled.

Cut pipe off 5' below ground level and weld on cap.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/30/65

INV. NO. 896-w

Signed: *Hugh Scott*
Well Plugging Supervisor