

15-175-10175-0000

Form CP-3
Rev. 6-26-62

KANSAS

Y
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 25 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Horizon Oil & Gas Company

Complete Address: Box 7, Spearman, Texas 79081

Lease Name Adams "A" Well No. 1-36

Location C NE NW Sec. 36 Twp. 34 Rge. 31 (E) (W)

County Seward Total Depth 6253'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: None

Plugging Contractor: Daco Lease & Well Service

Address: Borger, Texas License No. 138

Operation Completed: Hour 6:30PM Day 22 Month 4 Year 1968

The Above well was plugged as follows:

<u>8 5/8" to 1400' circulated w/ cement.</u>	<u>4 1/2" to 6244' cemented</u>
<u>Top perforations 6103'</u>	<u>Plug bottom w/ 10 sacks cement</u>
<u>Top of cement 6000'</u>	<u>Mud 6000' to 690'</u>
<u>Spotted 40 sacks cement 690' to 570'</u>	<u>Mud 570' to 35'</u>
<u>Plug, Halls & 75 sacks cement 35' to 0'</u>	<u>Company Pump</u>
<u>Pulled 3519' of 4 1/2" casing.</u>	

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edgar J. Cook*
Well Plugging Supervisor

DATE 4/26/68
INV. NO. 7643-W