

15-175-00081-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Ted R. Lofland

Complete Address R. R. 1-Box 85, Liberal, Kansas 67901

Lease Name Jenettie Long Well No. 1

Location C NW NW Sec. 33 Twp. 34 Rge. 31 (E) (W)

County Seward Total Depth 6800'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated None

Plugging Contractor Daco Lease & Well Service

Address Borger, Texas License No. 138

Operation Completed: Hour 2:00PM Day 13 Month 2 Year 1973

The above well was plugged as follows:

13 3/8" to 675' circulated w/ cement. 9 5/8" to 2646' cemented.

5 1/2" to 6050' cemented. Top perforations 5959 to 85'

Plug bottom w/ 20 sacks cement. Top of cement approx 5000'

Mud 5000' to 417' Spotted 60 sacks cement 417' to 300'

Mud 300' to 45' Bridge & 25 sacks cement 45' to 0'.

Company Pump Pulled 417' of 9 5/8" casing and 2701'

of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Coles
Well Plugging Supervisor

INVOICED

DATE 2/16/73

INV. NO. 6983-W