

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 19 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company

Complete Address: Box 1098, Liberal, Kansas

Lease Name Fitzgerald "A" Well No. 2

Location C NW SE Sec. 8 Twp. 34 Rge. 33 (E) (W)

County Seward Total Depth 4560'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: None

Plugging Contractor: Rine Drilling Co.

Address: 300 W. Douglas, Wichita, Kansas License No. _____

Operation Completed: Hour 2:00AM Day 18 Month 9 Year 1968

The Above well was plugged as follows:

8 5/8" to 771' circulated w/ cement. Mud 4560' to 4350'

Spotted 30 sacks cement 4350' to 4250' Mud 4250' to 2900'

Spotted 125 sacks cement 2900' to 2475' Mud 2475' to 750'

Spotted 35 sacks cement 750' to 600' Mud 600' to 40'

Plug, Hulls & 10 sacks cement 40' to 0',

Halliburton Pump Truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 9-19-68

INV. NO. 2484-W