

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Panhandle Eastern Pipe Line Co.

Complete Address: Box 828, Liberal, Kansas

Lease Name Wood Well No. 1

Location G NE SW Sec. 36 Twp. 34 Rge. 32 (E) (W)

County Seward Total Depth 6605'

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 3:00PM Day 7 Month 9 Year 1967

The Above well was plugged as follows:

13 3/8" to 652' circulated w/ cement, 9 5/8" to 2599' cemented

5 1/2" to 6149' cemented, Top perforations 5103'

Plug bottom w/ 50 sacks cement, Top of cement 4900'

Mud 4900' to 191' Rock Bridge & 50 sacks cement 191' to 120'

Mud 120' to 30' Plug, Hulls & 25 sacks cement 30' to 0'

Pulled 2706' of 5 1/2" casing and 171' of 9 5/8" casing.

Company Pump.

RECEIVED  
CONSERVATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/12/67

INV. NO. 6291-W

SEP 11 1967  
9-11-57  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: Edward Eves  
Well Plugging Supervisor