

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JUL 09 1976

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

*Plugging without
issued - June 1, 1976*

CONSERVATION DIVISION
Wichita, Kansas

API Number 15 - - (of this well)

Operator's Full Name Pan Eastern Company

Complete Address PO Box 828, Liberal, Kansas 67901

Lease Name Breen Renew Well No. 1

Location NW. NE 54 Sec. 34 Twp. 34 Rge. (E) (W) 32

County Seward Total Depth 6300

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargent's Casing Pulling

Address 620.5 Lincoln, Liberal Kan 67901 License No. 511

Operation Completed: Hour 9:30 PM Day 5 Month July Year 1976

The above well was plugged as follows:

*There was 2407' of 8 1/8" surface casing and
655' of 13 3/8" surface casing. 5' set to 6155.
Perforation from 5965-5960 set cast iron bridge
at 5900'. Put 170# sand. Perforations from 5298-
5278, set cast iron bridge at 5000'. Put 200# sand.
1st plug at 2200' with 50 sacks cement. 2nd plug
at 600' with 35 sacks cement. 3rd plug at 400' with
20 sacks cement. There was 2805' of 5 1/2" salvaged &*

I hereby certify that the above well was plugged as herein stated.

1200' of 8 1/8" salvaged

Signed: Clarence Thomas
Well Plugging Supervisor

INVOICED

DATE 7-14-76

INV. NO. 3457-W