

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mallonee-Coppinger Operations, Inc.

Complete Address: 1207 Union National Building, Wichita, Kansas

Lease Name Warden Well No. 1

Location C NE NE Sec. 30 Twp. 34 Rge. 32 (E) (W)

County Seward Total Depth 6560'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 5:30PM Day 21 Month 10 Year 1966

The Above well was plugged as follows:

8 5/8" to 1298' circulated w/ cement. 4 1/2" to 5253' cemented,

Top perforations 5198' Plug bottom w/ 20 sacks cement.

Top of cement 5000' Mud 5000' to 700'

Spotted 40 sacks cement 700' to 580' Mud 580' to 35'

Plug, Hulls & 10 sacks cement 35' to 0' Company Pump.

Pulled 4388' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10/24/66
INV. NO. 4154-W