

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
DEC 4 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Anadarko Production Company

Complete Address Box 351, Liberal, Kansas

Lease Name McAhren "C" Well No. 1

Location C NE NW Sec. 24 Twp. 34 Rge. 33 (E) (W)

County Seward Total Depth 6413'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 5:00PM Day 29 Month 11 Year 1973

The above well was plugged as follows:

8 5/8" to 1570' circulated w/ cement. 4 1/2" to 6412' cemented.

Top perforations 6324' Plug bottom w/ 20 sacks cement.

Top of cement 6224' Mud 6224' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Company Pump

Pulled 4202' of 4 1/2" casing.

INVOICED

I hereby certify that the above well was plugged as herein stated.

INV. NO. 8248-W

Signed: [Signature]
Well Plugging Supervisor