

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 8 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Alpar Resources Inc.

Complete Address Box 906, Perryton, Texas 79070

Lease Name Wright Well No. 1

Location Ne se Sec. 23 Twp. 34 Rge. 33 (E) (W)

County Seward Total Depth 6700'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 5:00Pm Day 3 Month 1 year 1974

The above well was plugged as follows:

8 5/8" to 1621' circulated w/ cement. 4 1/2" to 6689' cemented.

Top perforations 5362' Plug bottom w/ 20 sacks cement

Top of cement 5100' Mud 5100' to 1000'

Spotted 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2830' of 4 1/2" casing.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 1/9/74

INV. NO. 8386-W

Signed: [Signature]
Well Plugging Supervisor