

R

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Gulf Oil Exploration & Production

Complete Address Box 121116-Okla., City, Okla. 73112

Lease Name Rice Davies Well No. 1-1

Location C SE NE Sec. 1 Twp. 34s Rge. 32 (E) (W) X

County Seward Total Depth 6300

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Daco Lease & Well Servicing Co.

Address 1406 S. Cedar, Borger, Texas, 79007 License No. 138

Operation Completed: Hour 10 Am. Day 13 Month 9 Year 1979

The above well was plugged as follows:

1500' 8 5/8" casing w/650 sax cement. 4 1/2" casing set at 6300' w/125
sax cement. Plug back to 6275'-Pref. at 6100' Squeeze w/150 sax cement.
Pref. at 5808' squeeze w/150 sax cement. Set cement retainer at 5689'-
Pipe collapsed at 5586' to 5591'-Shot pipe off at 2789'-Pump 50 sax
50/50 posmix cement w/6% gel in 4/12" casing from 2757' to 2789'-50
sax at 1475' to 1525'-25 sax cement at 700'-Bridge at 30' & 10 sax
cement. All cement 50/50 posmix w/6% gel. Recovered 2789' 4/12" casing.
Cemented by Daco.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9-26-79
INV. NO. 0541/w

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1979
Signed: [Signature]
Well Plugging Supervisor