

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-175-20,617-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Grey Corporation

Complete Address 1670 Broadway, Suite 3301, Denver Colo. 80202

Lease Name Nikolas Well No. 1

Location C-SE-SE-SW Sec. 20 Twp. 34 Rge. 32 (East)(West)

County Seward Total Depth 6580'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Raines Williams Oil Co.

Address 435 Page Court, 220 W. Douglas, Wichita Kansas 67202 License No. _____

Operation Completed: Hour: 11:00 PM Day: 1 Month: May Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

1st plug 1580' with 60 skb of cement. 2nd plug at 780' with 35 skb of cement. 3rd plug on solid bridge at 40' to 0' with 10 skb of cement. Then circulated 10 skb of cement in rat hole & 5 skb of cement in mouse hole. Then plugged the water well with 3 skb of cement. The cement used was common with 2% c.c. pumped through. Drill pipe with hole full of heavy mud. The plugging was accomplished by Western Cementing.

Amount of Surface Casing: 1556' of 8 1/2" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthie
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I didn't get

RECEIVED
STATE CORPORATION COMMISSION

MAY - 6 1982

CONSERVATION DIVISION
Wichita, Kansas

Signed: Paul A. Luthie
Conservation Division Agent

INVOICED

DATE 5-28-82

INV. NO. 245-W