

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

**RECEIVED**  
STATE CORPORATION COMMISSION

**AUG 18 1965**

**CONSERVATION DIVISION**  
Wichita, Kansas

Operator's Full Name Anadarko Production Company

Complete Address: P. O. Box 351, Liberal, Kansas

Lease Name Condit "B" Well No. # 1

Location C SW NW Sec. 18 Twp. 34 Rge. 32 (E) (W)W

County Seward Total Depth 6380'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Moran Bros.

Address: 1200 Oil & Gas Bldg., Wichita Falls, Texas License No.

Operation Completed: Hour 3:00pm Day 16th Month August Year 1965

The Above well was plugged as follows:

1599' of 8 5/8" surface pipe, cement circulated . Hole was mudded to  
700', 1st cementing plug, bridged with hulls, and cemented with 35 sacks.  
Hole was filled with drilling mud to 45', 2nd cementing plug, bridged  
with hulls on fluid at 45', and cemented with 15 sacks to the base of  
the cellar.

This cementing was done by Sun Cementing Company

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elving  
Well Plugging Supervisor

DATE 8/18/65

INV. NO. 1652-W