

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 07 1978

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - -

CONSERVATION DIVISION  
Wichita, Kansas  
(of this well)

Operator's Full Name Yucca Petroleum

Complete Address Box 2858, Amarilla, Texas 79105

Lease Name Platt Well No. 1

Location C SE NE Sec. 10 Twp. 34 Rge. (E) (W) 31

County Seward Total Depth 5880'

Abandoned Oil Well        Gas Well XX Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Midwest Casing Pulling

Address Sublette, Kansas License No. 677

Operation Completed: Hour 4 P Day 4 Month 2 Year 1978

The above well was plugged as follows:

Total Depth 5880' 8.5/8 csg set 1471' cwc 750 sk.

2 7/8 tbd set 5879' cw (unknown) PFS (5670'-5694')

Pumped 1/2 sk hulls & 5 sk cem down tbg. top of cem. 5480'

Cutoff & recovered 2854' of tbg. Filled hole with heavy mud.

Set 20 sk pem plug at (1400'-1330') thru tbg.

Set 20 sk cmt plug (900'-830') thru tbg.

Set 10 sk cmt plug from 40' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Messer  
Well Plugging Supervisor

DATE 2-8-78

INV. NO. 6929-W