

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Luck of Thomas & Brewer has this
date requested permission to plug the following described well:

Mr. Luck guarantees payment of the plugging fee.

Operator's full Name: Thomas & Brewer

Complete Address: Drawer 1177 Liberal, Kansas

Lease Name: Neptune Well No. 3

Location: SE SE Sec. 17 Twp. 33 Rge. 41 (E) (W)

County Morton Total Depth 5140 Oil Well x

Gas Well Input Well SWD Well D & A x Lost Hole

Mr. Luck was instructed to plug the well as follows:

8 5/8"-1588' Circulated w/cement. 4 1/2"-5140' Cemented. Perforations 5058' to 5064'

Plug bottom w/20 Sax. cement 5140' to 4950' Mud 4940' to 1650'

Spotted 50 Sax. cement 1650' to 1500'

Pulled @ 2900' 4 1/2" pipe. Company Pump.

This well is being left for salt water disposal well.

Very truly yours,

Hugh Scott
Conservation Division Agent