



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202  
8-2-83

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

15-175-20,649-0000

Dear Sir:

Mr. John Hanna of Anadarko Pro. Co has this date requested permission to plug the following described well:

Operator's Full Name: Anadarko Production Co.

Complete Address: Box 351, Liberal Kansas 67901

Lease Name: Hitch Well No. G9

Location: 1650' FSL-1320' FEL Sec. 3 Twp. 33 Rge. 34 (E) (4)

County: Seward Total Depth: 6258'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Hanna was instructed to plug the well as follows:

They cement circulated 1598' of 8 5/8" surface casing. 1st plug at 2800' with 125 sbs of cement. 2nd plug at 1650' with 35 sbs of cement. 3rd plug at 760' with 25 sbs of cement. 4th plug 40' to 0 on solid bridge. The plugs pumped through drill pipe with hole full of heavy mud. They also circulated 10 sbs in each the rat hole & mouse hole. Halliburton accomplished the plugging

Very truly yours,

RECEIVED  
STATE CORPORATION COMMISSION

AUG 10 1982

CONSERVATION DIVISION  
Wichita, Kansas

Paul A. Luthi  
Conservation Division Agent