

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 19 1965

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Sutton of Panhandle Eastern Pipe Line Co. has this

date requested permission to plug the following described well:

Mr. Sutton guarantees payment of the plugging fee.

Operator's full Name: Panhandle Eastern Pipe Line Co.

Complete Address: Box 828 Liberal, Kansas

Lease Name: Crawford Well No. # 1-32

Location: C NE Sec. 32 Twp. 33S Rge. 37 (W)

County Stevens Total Depth 2851' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Sutton was instructed to plug the well as follows:

12 1/2"-569' Circulated w/cement. 8 5/8"-2575' Cemented. 4 1/2"-1990'

Linner set bottom 4 1/2" to 2767' Plug back to 2767'

Plug bottom w/125 Sax.cement 2767' to 2363' Mud 2363' to 650'

Spotted 110' Sax.cement 650' to 485' Mud 485' to 30'

Plug, hulls, 15 Sax.cement 30' to 0

Very truly yours,

Conservation Division Agent