

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 30 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ken Davis of Daco Lease & Well Service has this date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: Sidwell Oil & Gas Inc.

Complete Address: Box 2475, Pampa Texas

Lease Name: Bath Well No. #1

Location: C. NW, NE Sec. 18 Twp. 33 Rge. 41 (D) (W) VII

County Marton Total Depth 5435 Oil Well —

Gas Well — Input Well — SWD Well — D & A — Lost Hole —

Mr. Davis was instructed to plug the well as follows:

8 5/8 set @ 1491 - Cement Circ.

4 1/2 " @ 5148 - perforated, 4998-5011

20 sbs cement on bottom

Mud to 700' Cement 35 sbs 700'-600'

Mud 600'-33' Cement 10 sbs 33'-3'

8 5/8 cut off @ 3'

4 1/2 pipe shot off @ 3914

Very truly yours,

Bill Spinnell
Conservation Division Agent