

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 4 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Luck of Thomas Inc. has this

date requested permission to plug the following described well:

Mr. Luck guarantees payment of the plugging fee.

Operator's full Name: Thomas Inc.

Complete Address: Box 526 Liberal, Kansas

Lease Name: Waddel Well No. # 1

Location: NE SE Sec. 19 Twp. 33S Rge. 41 (E) (W)

County Morton Total Depth 5430' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Luck was instructed to plug the well as follows:

8 5/8"-1496' Circulated w/cement.

Mud 5430' to 5070' Spotted 25 Sax.cement 5070' to 5000'

Mud 5000' to 700' Spotted 35 Sax.cement 700' to 600'

Mud 600' to 45' Plug, Hulls, 15 Sax.cement 45' to 0

Very truly yours,

[Signature]
Conservation Division Agent