

1 050210

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-175-20,754-0000

C E/2 E/2, SEC. 18, T 34 S, R 32 (W/E)

2640 feet from XN/S section line

660 feet from XN/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name Dodd Well # 2-18

Operator: Beren Corporation

County Seward

Name & Address 970 Fourth Financial Center

Well Total Depth 6090 197.93 feet

Wichita, KS 67202

Conductor Pipe: Size 18" feet 74

Surface Casing: Size 8 5/8 feet 1590

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor NRG Drilling, Inc. License Number 6666

Address Box 1157, Liberal, KS 67901

Company to plug at: Hour: Midnight Day: 5 Month: May Year: 19 84

Plugging proposal received from Fred Paine

(company name) NRG (phone) 316-624-1818

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2500' with 50 sx cement

2nd plug at 1620' with 40 sx cement

3rd plug at 810' with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by Richard W. Lacy  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4:45 am Day: 5 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2500' with 50 sx cement, 2nd plug at 1620' with 40

sx cement, 3rd plug at 810' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' cement to surface with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

(If necessary, please observe this plugging.)

**INVOICED**

DATE 5-14-84

INV. NO. 1493

5-5 MAY 23 1984

Signed Richard W. Lacy  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 11 1984  
CONSERVATION DIVISION  
Wichita, Kansas