

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20476-00-01  
Spot: CNWSW Sec/Twnshp/Rge: 18-34S-32W  
1980 feet from S Section Line, 660 feet from W Section Line  
Lease/Unit Name: DODD B Well Number: 2  
County: SEWARD Total Vertical Depth: 6405 feet

Operator License No.: 4549  
Op Name: ANADARKO PETROLEUM CORPORATI  
Address: 1201 LAKE ROBBINS DRIVE  
THE WOODLANDS, TX 77380

Production Casing Size: 5.5 feet: 6404 WITH 400 SX CMT  
Surface Casing Size: 8.625 feet: 1572 WITH 800 SX CMT

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/31/2003 3:00 PM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 25 SX CMT FOR BOTTOM PLUG. PLUG AT 1600' WITH 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 04/01/2003 1:00 PM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 6216'. PERFS AT 6315-6324, 6253-6271, 5178-5192, 5004-5008. CIBP @ 6300'. CMT RETAINER @ 6216'. TOC @ 4400'. PUMP 400# HULLS & 25 SX CMT FOR BOTTOM PLUG. 1ST PLUG AT 1600' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED  
APR 08 2003  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2211' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
APR - 2 2003  
KCC Dodge City

Signed Jim Holland (TECHNICIAN)

INVOICED  
DATE 4-9-03  
INV. NO. 2003061398

Form 6727