

1 100153

8-28

API NUMBER 15- Docket #D-25,235-0000

To: STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION App. SW NW SW, SEC. 15, T 34 S, R 32 W
130 S. Market, Room 2078
Wichita, KS 67202

1600 feet from S section line
5000 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 30606

Lease Name Yeager Well # 2

Operator: Murfin Drilling Co., Inc.

County Seward 49.24

Name & Address 250 N. Water, Ste. 300

Well Total Depth 1515 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 85

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Quality Well Service License Number 31925

Address 249 E. Beth Dr., Sterling, KS 67579

Company to plug at: Hour: 7 p.m. Day: 28 Month: 8 Year: 19 97

Plugging proposal received from Richard McIntyre

(company name) Quality Well Service (phone) 316-278-2476

Work: 5 1/2" at 1514' w/275 sx cement (cemented to surface), PBTD 1473', Perfs at 1060-1126'

1st plug pump 300 lbs. hulls and 155 sx cement to fill casing,

Check backside.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 7:30 p.m. Day: 28 Month: 8 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls and 155 sx cement to fill casing from top to bottom. Shut in with 500 psi on casing.

2nd plug pumped 30 sx cement down backside to top off. Pressured up to 250 psi. Left shut in.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery. (If additional description is necessary, use BACK of this form.)

INVOICED I (did / observe this plugging.

DATE 9-5-97

Signed Gary Winters (TECHNICIAN)

INV. NO. 48931