

1 060542

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,592-0000 *R*
S/2 NE SW, SEC. 15, T 34 S, R 32 W/E

1650 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5760

Lease Name Yeager Well # 2

Operator: Irex Corporation

County Seward *206.44*

Name & Address 1331 17th Street, Suite 800

Well Total Depth 6352 feet

Denver, CO 80202

Conductor Pipe: Size 20" feet 77'

Surface Casing: Size 8 5/8 feet 1510

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Reeves & Wilson License Number 6083

Address 3401 Willow West, Woodward, OK 73801

Company to plug at: Hour: 4:00 pm Day: 17 Month: April Year: 1985

Plugging proposal received from Mark Pennick

(company name) Reeves & Wilson (phone) 405-256-6023

were: 4 1/2" at 6336' PBSD 6303' Open Hole 6336-6352'

1st plug set CIBP at 6300' with 2 sx cement in 4 1/2"

Pump through 4 1/2" with mud in between plugs

RECEIVED
STATE CORPORATION COMMISSION

2nd plug at 2995' with 40 sx cement 3rd plug at 1560' with 40 sx cement

APR 23 1985

4th plug at 860' with 40 sx cement 5th plug solid bridge

CONSERVATION DIVISION
Wichita, Kansas

with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:00 pm Day: 17 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug set CIBP at 6300' with 2 sx cement in 4 1/2" casing,

2nd plug at 2995' with 40 sx cement, 3rd plug at 1560' with 40 sx cement, 4th plug at

860' with 40 sx cement, 5th & 6th plugs - solid bridge - hulls - plug at 40' --- cement

to surface with 10 sx cement.

Remarks: Recovered 2995' 4 1/2" casing. Used Class H Cement by Reeves & Wilson

(If additional description is necessary, use BACK of this form.)

(old / ~~APR 23 1985~~) observe this plugging.

INVOICED
DATE 5-3-85

Signed Paul A. Luthie
(TECHNICIAN)

INV. NO. 7924
4-17-85 MAY 22 1985