

8-28

To: 100152
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 175-20,542- 0000

C NW SW, SEC. 15, T 34 S, R 32 W/E

1980 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 30606

Lease Name Yeager Well # 1

Operator: Murfin Drilling Co., Inc.

County Seward 205.92

Name & Address 250 N. Water, Ste. 300

Well Total Depth 6336 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1572

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Quality Well Service License Number 31925

Address 249 E. Beth Dr., Sterling, KS 67579

Company to plug at: Hour: 2 p.m. Day: 28 Month: 8 Year: 19 97

Plugging proposal received from Richard McIntyre

(company name) Quality Well Service (phone) 316-278-2476

Work: 5 1/2" at 6324' w/200 sx cement, PBD 6100', Perfs at 6260-61, 6324-36'

1st plug cement through tubing at 1763' to surface, pull tubing,

2nd plug top off hole.

Plugging Proposal Received by Scott Alberg (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 6 p.m. Day: 28 Month: 8 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 6100' with 2 sx cement,

2nd plug pumped 100 sx cement and displaced to 2900' with mud, 3rd plug pumped 50 sx cement and spotted to 1600',

4th plug pumped 50 sx cement and spot to 700',

5th plug pumped 10 sx cement and topped off at 40-0'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3226' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

INVOICED

DATE: 9-8-97

Signed Gary Winters (TECHNICIAN)

INV. NO. 48930