

2-9

To: 1 051269  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO STORBY BUILDING  
WICHITA, KANSAS 67202  
TECHNICIAN'S PLUGGING REPORT

API NUMBER 15- 151-20,950-60-00  
NE NW NE, SEC. 24, T 27 S, R 15 W/E  
4950 feet from S section line  
1650 feet from E section line

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 14 1990

Operator License # 3476  
Operator Name Oil Company  
Address 318 North Ninnescah  
Pratt, KS 67124

Lease Name Jones Well # 1-24  
County Pratt 153.30  
Well Total Depth 4717 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well Gas Well  Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Service License Number 6050  
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 9 Month: 2 Year: 19 90

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling Service (phone) 316-938-2943

were: 4 1/2" at 4642' PBD 4642' Perfs at 4432-46'

1st plug sand back to 4380' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 12 p.m. Day: 9 Month: 2 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4380' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Maximum pressure 125 psi and shut in 125 psi.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 14 1990

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2200' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-15-90

Signed Richard M. Lacey (TECHNICIAN)

INV. NO. 27461  
2-9