

1 010166

X 168R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,335-00-20  
SE SE SW, SEC. 24, T 27 S, R 15 W/E  
330 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171  
Operator: TXO Production Corporation  
Name & Address: 155 N. Market, Suite 1000  
Wichita, Ks 67202

Lease Name Schnoover Well # 1  
County Pratt 149.27  
Well Total Depth 4593 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 432

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor TXO Production Corp. License Number 5171

Address 155 N. Market, Suite 1000, Wichita, KS 67202

Company to plug at: Hour: 8:20 a.m. Day: 29 Month: 8 Year: 19 86

Plugging proposal received from Jerry Collins'

(company name) TXO (phone) 316-265-9441

were: 4 1/2" at 4592' PBTD 4581 Perfs at 4432-44' Elevation 2037'GL

1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer

2nd plug squeezed well with 1 sx hulls, mixed 2 sx hulls with 100 sx of thrifty mix.

Plugging Proposal Received by Jack Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:00 a.m. Day: 29 Month: 8 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 4 sx of cement on top of sand through bailer

2nd plug squeezed well with 1 sx hulls, mixed 2 sx hulls in with 100 sx of thrifty mix.

weight of cement - 12.5 lbs.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Recovered 3000' of 4 1/2" casing. Used thrifty mix (12.5 lbs.) by B.J. Titan. (If additional description is necessary, use BACK of this form.)

INVOICED (void) observe this plugging.

DATE 9-3-86

INV. NO. 14872

SEP 3 1986 09-03-86

Signed [Signature] (TECHNICIAN)