

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-19010-00-00
Spot: SWNESW Sec/Twnshp/Rge: 23-27S-15W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: VERNING ESTATE Well Number: 1
County: PRATT Total Vertical Depth: 4603 feet

Operator License No.: 7701

Conductor Pipe: Size feet: 3 1/4 9.60

Op Name: G.L.E. CORP.

Surface Casing: Size 8.625 feet: 295

Address: 518 WASHINGTON ST.
PRATT, KS 67124

Production: Size 5.5 feet: 4603

Liner: Size feet:

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 03/22/2002 1:30 PM

Plug Co. License No.: 5105

Plug Co. Name: CLARKE CORPORATION

Proposal Rcvd. from: ALAN VRATIL

Company: CLARKE CORPORATION

Phone: (620) 886-5665

Proposed Plugging Method: SAND BACK TO 4400' WITH 4 SX CMT. 1ST PLUG AT 950' WITH 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. USE 10 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 03/22/2002 2:30 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 4454-4462'. SANDED BACK TO 4380' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. LAID DOWN CASING AND RUN 2 3/8" TUBING IN TO SPOT PLUGS. 1ST PLUG AT 950' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 25 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2200' OF 4 1/2" CASING.

Plugged through: TBG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

RECEIVED

MAR 25 2002

DATE March 28-02

MAR 28 2002

TW. NO. 2002061579

KCC WICHITA

AP

2/3