

To: 1 100181
STATE CORPORATION COMMISSION 12-10
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-175-21,644-0000
C NE SW, SEC. 8, T 34 S, R 31 W/E
1980 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name:
Address P.O. Box 351
Liberal, KS 67905-0351

Lease Name McClure J Well # 1
County Seward 201.50
Well Total Depth 6200 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1514

Abandoned Oil Well Gas Well X Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 8 a.m. Day: 8 Month: 12 Year: 19 97

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 5 1/2" at 6099' w/180 sx cement, PBD 5865', Perfs at 5688-5846'
1st plug pump 4 sx hulls and 25 sx cement at 5685',
2nd plug at 3000' with 100 sx cement,
3rd plug at 1530' with 50 sx cement,
4th plug at 650' with 40 sx cement, 5th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Gary Winters
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11 a.m. Day: 10 Month: 12 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug spotted 25 sx cement with 400 lbs. hulls from 5688-5488',
displaced with gel,
2nd plug spotted 100 sx cement at 3000', displaced with gel,
3rd plug spotted 50 sx cement at 1530-1380', displaced with gel,
4th plug spotted 40 sx cement at 650-550', displaced with gel,
5th plug spotted 10 sx cement at 40-0'.

Remarks: Used common cement by Sargent & Horton. Recovered 4024' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~XXXXXX~~) observe this plugging.

DATE DEC 18 1997

INV. NO. 49733

Signed Gary Winters
(TECHNICIAN)

12-10