

1100250

TO: STATE CORPORATION COMMISSION

API NUMBER 15-175-21,071-0000
NW SW NE SEC. 30, T 34 S, R 34 W

10-21

CONSERVATION DIVISION - PLUGGING SECTION 3406 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2086 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME WOODMAN WELL # C-2

TECHNICIAN'S PLUGGING REPORT COUNTY SEWARD 217.75

OPERATOR LICENSE # 5941 WELL TOTAL DEPTH 6700 FEET

OPERATOR: ROSEL ENERGY, INC PRODUCTION CSG: SIZE 4 1/2" @ 6504' WITH 775 SX

NAME AND 302 S CLAY SURFACE CASING: SIZE 8 5/8" @ 1688' WITH 250 SX

ADDRESS LIBERAL, KS 67901

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING SERVICE LICENSE NUMBER N/A

ADDRESS PO BOX 628, GREAT BEND, KS 67530

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 21 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM HAROLD FRAULI

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: PERFS AT 2704-2825 MARKER DEPTH @ 1650'.

1ST PLUG SET CIBP AT 2660' WITH 2 SX CEMENT ON TOP.

2ND PLUG AT 1676' WITH 50 SX CEMENT.

3RD PLUG AT 630' WITH 50 SX CEMENT.

4TH PLUG AT 40'-0' WITH 15 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 21 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP AT 2660' WITH 2 SX CEMENT ON TOP.

2ND PLUG AT 1676' WITH 50 SX CEMENT.

3RD PLUG AT 630' WITH 50 SX CEMENT.

4TH PLUG AT 40'-0' WITH 15 SX CEMENT.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2088' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Gary Winters (TECHNICIAN) FORM CP-2/3

RECEIVED
KANSAS CORP COM
JAN 10 1998

11-5-98
60266 10-21 JAN 29 1999