

1100251

TO: STATE CORPORATION COMMISSION

10-20

API NUMBER 15-175-20,866 A-0001
NE NW NE SEC. 30, T 34 S, R 34 W

CONSERVATION DIVISION - PLUGGING SECTION 4726 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1874 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME WOODMAN WELL # C-1

TECHNICIAN'S PLUGGING REPORT

COUNTY SEWARD 213,20

OPERATOR LICENSE # 5941

WELL TOTAL DEPTH 6560 FEET

OPERATOR: ROSEL ENERGY, INC

PRODUCTION CSG: SIZE 4 1/2" @ 6560' WITH 700 SX

NAME AND 302 S CLAY

SURFACE CASING: SIZE 8 5/8" @ 1662' WITH 150 SX

ADDRESS LIBERAL, KS 67901

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING SERVICE LICENSE NUMBER N/A

ADDRESS PO BOX 628, GREAT BEND, KS 67530

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 20 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM HAROLD FRAULI

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: PERFS AT 2760-3138

1ST PLUG SET CIBP AT 2660' WITH 2 SX CEMENT ON TOP.

2ND PLUG AT 1600' WITH 50 SX CEMENT.

3RD PLUG AT 650' WITH 50 SX CEMENT.

4TH PLUG AT 40'-0' WITH 15 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 20 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP AT 2660' WITH 2 SX CEMENT ON TOP.

2ND PLUG AT 1600' WITH 50 SX CEMENT.

3RD PLUG AT 650' WITH 50 SX CEMENT.

4TH PLUG AT 40'-0' WITH 15 SX CEMENT.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1620' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Gary Winters (TECHNICIAN) FORM CP-2/3

RECEIVED KANSAS CORP COM

11-5-98 60266

10-20 JAN 29 1999